



1st Floor
36 Bennetts Hill
Birmingham
B2 5SN

Project Number	LP2408
Project Name	PETERCHURCH PRIMARY SCHOOL
Project Area	HEREFORDSHIRE

Specification Title	Discipline	Document	Clause No.	Ref	Rev	Q31
TREE SCHEDULE - Semi-Mature	LA			Q31	P02	
	Document Status		PLANNING			

Filename	100583-FIR-EX-XX-T-L-7001	Author	Checked Date	Initials	Authorised Date	Initials
		AJS	30.01.25	JP	30.01.25	JP

[illegible]



Landscape architecture & urban design				1st Floor, 36 Bennetts Hill, Birmingham, B2 5SN			
Job No.:	Project Name	Issue Status	Author	Checked	Date	Revision	Filename
LP2408	PETERCHURCH PRIMARY SCHOOL	PLANNING	AJS	JP	30.01.25	P02	100583-FIR-EX-XX-T-L-7001
	HEREFORDSHIRE						
ABBREVIATIONS USED IN THE SCHEDULE:		T= Transplant, W= Whip, F= Feathered, HS= Half Standard, S= Standard, SS= Select Standard, HS= Heavy Standard, EHS= Extra Heavy Standard, SM= Semi Mature, MS= Multi-Stemmed, O= Open Ground, W= Root Wrapped, WRB= Wire Rootball					
Notes:		Trees should only be planted during the appropriate Season between late October and late March. Trees should NOT be planted 'out of season' unless agreed with the Landscape Architect. Trees should only be Planted while soil and weather conditions are suitable and NOT during periods of frost or strong winds					
TREE SCHEDULE - Semi-Mature							
Species	Girth and Height (cm)	Times Transplanted	Clear Stem (CS) or Feathered (F)	Classification	Notes	Quantity No.	Rate
Acer campestre	14-16	3x	CS	EHS/WRB (600mm)	Uniform canopy, strong leader	7	
Betula pendula	14-16	3x	CS	EHS/WRB (600mm)	Matching height and spread	7	
Fagus sylvatica	14-16	3x	CS	EHS/WRB (600mm)	Specimen full shape to ground	2	
Prunus avium	14-16	3x	CS	EHS/WRB (600mm)	Avenue matching crown shape/height	3	
Prunus serrula	14-16	3x	CS	EHS/WRB (600mm)	Matching height and spread	6	
Ulmus 'New Horizon'	14-16	3x	CS	EHS/WRB (600mm)	Uniform canopy, strong leader	4	