



Gladman Developments Limited

Pencombe Lane, Bromyard

Arboricultural Assessment

August 2019

FPCR Environment and Design Ltd

Registered Office: Lockington Hall, Lockington, Derby DE74 2RH

Company No. 07128076. [T] 01509 672772 [F] 01509 674565 [E] mail@fpcr.co.uk [W] www.fpcr.co.uk

This report is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without the written consent of FPCR Environment and Design Ltd. Ordnance Survey material is used with permission of The Controller of HMSO, Crown copyright 100018896.

Rev	Issue Status	Prepared / Date	Approved/Date
-	Draft	TJR / 17.06.14	TJR / 17.06.14
-	Final	TJR / 03.07.14	TJR / 03.07.14
A	Final	CTT / 10.08.16	TJR / 10.08.16
B	Final	CTT / 09.10.18	TCB / 09.10.18
C	Final	CTT / 08.08.19	GEC / 08.08.19

CONTENTS

INTRODUCTION.....	2
2.0 PLANNING POLICY.....	3
3.0 SURVEY METHODOLOGY.....	4
4.0 RESULTS	9
5.0 ARBORICULTURAL IMPACT ASSESSMENT	11
6.0 NEW TREE AND HEDGEROW PLANTING.....	13
7.0 TREE PROTECTION MEASURES	15

TABLES

Table 1: Summary of Trees by Retention Category

PLANS

Tree Survey Plan (6158-A-02)

Tree Retention Plan (6158-A-03C)

APPENDICES

Appendix A: Tree Schedule

Appendix B: Protective Fencing Specifications

INTRODUCTION

- 1.1 This report has been prepared by FPCR Environment and Design Limited on behalf of Gladman Developments Limited to present the findings of an Arboricultural Assessment and survey of trees located at Pencombe Lane, Bromyard (hereafter referred to as the site), OS Grid Ref SO 643 543. The original survey and assessment was carried out on 1st May 2014 with a subsequent updated resurvey carried out on 2nd August 2016.
- 1.2 The tree survey and assessment of existing trees has been carried out in accordance with guidance contained within British Standard 5837:2012 '*Trees in Relation to Design, Demolition and Construction - Recommendations*' (hereafter referred to as BS5837). The guidelines set out a structured assessment methodology to assist in determining which trees would be deemed either as being suitable or unsuitable for retention.
- 1.3 The guidance also provides recommendations for considering the relationship between existing trees and how those trees may integrate into designs for development; demolition operations and future construction processes so that a harmonious and sustainable relationship between any retained trees and built structures can be achieved.
- 1.4 The purpose of the report is therefore to firstly present the results of an assessment of the existing trees' arboricultural value, based on their current condition and quality and to secondly provide an assessment of impact arising from the proposed development of the site.

Site Description

- 1.5 The site was in Bromyard, a town in north east Herefordshire, and comprised two field parcels currently open agricultural grassland. The northern boundary was formed by the A44, the eastern boundary was formed by existing residential properties, the southern boundary by Pencombe Lane and the western boundary by further field parcels.
- 1.6 The presence of any Tree Preservation Orders or Conservation Area designations that may affect the site has yet to be confirmed by Herefordshire Council. Once this information has been received, the report will be updated accordingly. Before any tree works are undertaken confirmation of the presence of the statutory constraints should be sought from the Local Authority.

2.0 PLANNING POLICY

National Planning Policy Framework 2019

- 2.1 National Planning Policy is defined by the National Planning Policy Framework (NPPF). This sets out the Government's most current and up to date planning policies for England and how these should be applied. The current NPPF is dated February 2019.
- 2.2 Paragraph 11 of the NPPF states that there is a presumption in favour of sustainable development and states that for decision making, the LPA should be '*c) approving development proposals that accord with an up-to-date development plan without delay*'. In the absence of a development plan or the development plan is out of date, the acting LPA should grant planning consent so far as the development proposals do not breach the policies and guidance outlined in the NPPF.
- 2.3 In relation to arboriculture, the NPPF also states that:
- 175(c) '*development resulting in the loss or deterioration of irreplaceable habitats (such as ancient woodland and ancient or veteran trees) should be refused, unless there are wholly exceptional reasons and a suitable compensation strategy exists*';
- and provides specific guidance that:
- 175(d) '*development whose primary objective is to conserve or enhance biodiversity should be supported; while opportunities to incorporate biodiversity improvements in and around developments should be encouraged, especially where this can secure measurable net gains for biodiversity*'.
- 2.4 Examples of what is deemed to be '*wholly exceptional*' are included within Footnote 58 and provides the examples of '*infrastructure projects (including nationally significant infrastructure projects, orders under the Transport and Works Act and hybrid bills), where the public benefit would clearly outweigh the loss or deterioration of habitat*'.

Statutory Considerations

- 2.5 Local authorities have a Duty under the Town and Country Planning Act to create Tree Preservation Orders (TPO) in order to protect and preserve specific trees and woodlands that bring significant amenity benefit to a particular site or location. Under a TPO it is a criminal offence to cut down, top, lop, uproot or willfully destroy a tree protected by that Order, or to cause or permit such actions, if carried out without the prior written consent of the acting LPA. Anyone found guilty of such an offence is liable and in serious cases, may result in prosecution and incur an unlimited fine.
- 2.6 The presence of any Tree Preservation Orders or Conservation Area designations that may affect the site has yet to be confirmed by Herefordshire Council. Once this information has been received, the report will be updated accordingly. Before any tree works are undertaken confirmation of the presence of the statutory constraints should be sought from the Local Authority.

3.0 SURVEY METHODOLOGY

- 3.1 The survey of trees has been carried out in accordance with the criteria set out in Chapter 4 of BS5837. The survey has been undertaken by a suitably qualified and experienced arboriculturist and has recorded information relating to all those trees within the site and those adjacent to the site which may be of influence to any proposals. Trees were assessed for their arboricultural quality and benefits within the context of the proposed development in a transparent, understandable and systematic way.
- 3.2 Trees have been assessed as groups or hedgerows where it has been determined appropriate.
- The term group has been applied where trees form cohesive arboricultural features either aerodynamically, visually or culturally including biodiversity or habitat potential for example parkland or wood pasture.
 - For the purposes of this assessment, a hedgerow is described as any boundary line of trees or shrubs less than 5m wide at the base and are managed under a regular pruning regime.
 - For the purposes of this assessment woodland is described as a habitat where ‘trees are the dominant plant form. The individual tree canopies generally overlap and interlink, often forming a more or less continuous canopy’¹. Woodlands however, are not just formed of trees and generally include a great variety of other plants. These will include ‘mosses, ferns and lichens, as well as small flowering herbs, grasses and shrubs’².
- 3.3 An assessment of individual trees within groups or hedgerows has been made where a clear need to differentiate between them, for example, in order to highlight significant variation between attributes including physiological or structural condition or where a potential conflict may arise.

Ancient and Veteran Trees

- 3.4 Veteran trees and Ancient Woodland are important components of the landscape, their importance can be for a number of reasons including that of their ecological, social, cultural and historic value.
- 3.5 Veteran Trees and Ancient Woodlands are material considerations within the planning process and their importance is specifically recognised within the National Planning Policy Framework (NPPF) 2019, which defines the terms ancient or veteran tree as:
- ‘A tree which, because of its age, size and condition, is of exceptional biodiversity, cultural or heritage value. All ancient trees are veteran trees. Not all veteran trees are old enough to be ancient, but are old relative to other trees of the same species. Very few trees of any species reach the ancient life-stage.’³*
- 3.6 Various published methodologies are currently available which, due to the complexity and subjectivity of the process of defining and assessing these trees, often have conflicting definitions. This assessment, and the criteria used for defining ancient/veteran trees and the identification of attributable ancient/veteran features, has been based on a range of currently published guidance and resources.

¹ http://www.countrysideinfo.co.uk/woodland_manage/whatis.html

² http://www.countrysideinfo.co.uk/woodland_manage/whatis.html

³ Ministry of Housing, Communities and Local Government. (2019). *National Planning Policy Framework*. London: Ministry of Housing, Communities and Local Government.

Ancient Tree

- 3.7 The definition of an ancient tree has been based on Ancient Tree Guide No. 4 (ATF, 2008) which suggest ancient should be used for a tree that:

'has passed beyond maturity and is old, or aged, in comparison with other trees of the same species.

- 3.8 Perhaps most notably, the tree concerned should be very old, relative to others of the same species.

- 3.9 Further to this, in accordance with guidance for use in the Ancient Tree Hunt (Owen & Alderman, 2008), as cited within Lonsdale (2013)⁴ an ancient tree is one that has all or most of the following characteristics:

- a) biological, aesthetic or cultural interest, because of its great age;
- b) a growth stage that is described as ancient or post-mature; or
- c) a chronological age that is old relative to others of the same species.

Guided by Lonsdale (2013)⁶ characteristics a) and b) are mainly based on developmental and morphological criteria whilst characteristic c) relates specifically to chronological age. Developmental characteristics (represented by characteristic b) above) tend to develop with the increasing age of a tree and include:

- A large girth by comparison with other trees of the same species⁵
- Aging and associated decay (leading to hollowing) of the central wood
- Changes in crown architecture (Raimbault, 2006)⁶
- A progressive or episodic reduction in post-mature crown size - 'retrenchment' (Lonsdale 2004; Rust & Roloff, 2002)

In practice calculating the average age / lifespan of a tree is difficult and not always entirely reliable due to a lack of available demographic information. As such, in order to inform the assessment of chronological age, the assessment has made use of stem girth as a guide using the chart provided within Lonsdale (2013).

Veteran Trees

- 3.10 The definition of a veteran tree has been based on within Lonsdale (2013) as a tree:

'which has survived various rigours of life and thereby shows signs of ancientness, irrespective of its age'.

^{4, 6} Lonsdale, D. (Ed.). 2013). Ancient and other veteran trees: further guidance on management. London: The Tree Council.

⁵ Woodland Trust, Ancient Tree Forum (2008). Ancient Tree Guide no.4: What are ancient, veteran and other trees of special interest?. Grantham: Unknown. 7.

⁶ Raimbault, P.F. (2006). A basis for morpho-physiological tree assessment. Pro. Seminar, Arboricultural Association/Treework Environmental Practice, Ashton Court, Bristol, UK, 23rd & 24th March 2006.

- 3.11 However, for the purpose of the BS5837:2012 assessment, to qualify as a veteran tree, the tree concerned requires a stem girth which is considered large for its species (within the range set out in Fig. 1 above) and shows signs of crown retrenchment and evidence of decay processes in stem, branches or roots such as dead and decaying wood or fungal fruiting bodies of heart-rot (wood decay) species. These trees should also possess significant amounts of dead wood in the crown or fallen about the ground beneath the trees crown.
- 3.12 In principal, reference has been made to Owen & Alderman (2008) and Reed, H. (2000). *Veteran Trees: A Guide to Good Management*. English Nature and more recently Lonsdale, D (ed.) (2013) *Ancient and other Veteran Trees: Further Guidance on Management*, The Tree Council & Ancient Tree Forum for guidance on the recognition of both ancient and veteran trees.
- 3.13 Level 3 of the Specialist Survey Method (SSM) of de Berker & Fay (2004)⁷ has also been utilised for gathering survey information as this provides a standardised framework for recording characteristic ancient/veteran features.
- 3.14 **No Ancient or Veteran trees were identified as part of this assessment.**

BS5837 Categories

- 3.15 Trees have been divided into one of four categories based on Table 1 of BS5837, '*Cascade chart for tree quality assessment*'. For a tree to qualify under any given category it should fall within the scope of that category's definition (see below).
- 3.16 Category U trees are those which would be lost in the short term for reasons connected with their physiology or structural condition. They are, for this reason not considered in the planning process on arboricultural grounds. Categories A, B and C are applied to trees that should be of material considerations in the development process. Each category also having one of three further sub-categories (i, ii, iii) which are intended to reflect arboricultural, landscape and cultural or conservation values accordingly.
- 3.17 **Category (U) – (Red):** Trees which are unsuitable for retention and are in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years. Trees within this category are:
- Trees that have a serious irremediable structural defect such that their early loss is expected due to collapse and includes trees that will become unviable after removal of other category U trees.
 - Trees that are dead or are showing signs of significant, immediate or irreversible overall decline.
 - Trees that are infected with pathogens of significance to the health and/ or safety of other nearby trees or are very low quality trees suppressing adjacent trees of better quality.
 - Certain category U trees can have existing or potential conservation value which may make it desirable to preserve.

⁷ de Berker, N., & Fay, N. (2004). English Nature Research Report Number 529 – Evaluation of the Specialist Survey Method for Veteran Tree Recording. Bristol: Treework Environmental Practice.

- 3.18 **Category (A) – (Green):** Trees that are considered for retention and are of high quality with an estimated remaining life expectancy of at least 40 years with potential to make a lasting contribution. Such trees may comprise:
- Sub category (i) trees that are particularly good examples of their species, especially if rare or unusual, or are essential components of groups such as formal or semi-formal arboricultural features for example the dominant and/or principal trees within an avenue.
 - Sub category (ii) trees, groups or woodlands of particular visual importance as arboricultural and / or landscape features.
 - Sub category (iii) trees, groups or woodlands of significant conservation, historical, commemorative or other value for example veteran or wood pasture.
- 3.19 **Category (B) – (Blue):** Trees that are considered for retention and are of moderate quality with an estimated remaining life expectancy of at least 20 years with potential to make a significant contribution. Such trees may comprise:
- Sub category (i) trees that might be included in category A but are downgraded because of impaired condition for example the presence of significant though remediable defects, including unsympathetic past management and storm damage.
 - Sub category (ii) trees present in numbers, usually growing as groups or woodlands, such that they attract a higher collective rating than they might as individuals or trees occurring as collectives but situated so as to make little visual contribution to the wider locality.
 - Sub category (iii) trees with material conservation or other cultural value.
- 3.20 **Category (C) – (Grey):** Trees that are considered for retention and are of low quality with an estimated remaining life expectancy of at least 10 years or young trees with a stem diameter below 150mm. Such trees may comprise:
- Sub category (i) unremarkable trees of very limited merit or such impaired condition that they do not qualify in higher categories.
 - Sub category (ii) trees present in groups or woodlands, but without this conferring on them significantly greater collective landscape value or trees offering low or only temporary / transient screening benefits.
 - Sub category (iii) trees with no material conservation or other cultural value.

Tree Schedule

- 3.21 Appendix A presents details of any individual trees, groups, hedgerows and woodlands found during the assessment including heights, diameters at breast height, crown spread (given as a radial measurement from the stem), age class, comments as to the overall condition at the time of inspection, BS5837 category of quality and suitability for retention and the root protection area.
- 3.22 General observations particularly of structural and physiological condition for example the presence of any decay and physical defect and preliminary management recommendations have also been recorded where appropriate.

Site Plans

- 3.23 The individual positions of trees and groups have been shown on the Tree Survey Plan. The positions of trees are based on a topographical / land survey, as far as possible, supplied by the client. Where topographical information has not identified the position of trees these have been plotted using a global positioning system and aerial photography to provide approximate locations. The crown spread, root protection area and shade pattern (where appropriate) are also indicated on this plan.
- 3.24 As part of this assessment, a Tree Retention Plan has been prepared to show the proposed layout in relation to the existing tree cover allowing an assessment of any potential conflicts. The plan also identifies which trees would be required to be removed or retained as part of the proposed development.

Tree Constraints and Root Protection Areas

- 3.25 Below ground constraints to future development are represented by the area surrounding the tree containing sufficient rooting volume for the specimen to have the best chance of survival in the long term which is identified as the root protection area (RPA). The RPA has been calculated in accordance with section 4.6 of BS5837 and requires suitable protection in order for the tree to be successfully incorporated into any future scheme.
- 3.26 Where applicable the shape of the Root Protection Area has been modified to consider the presence of any nearby obstacles (existing or past) which may have restricted root growth and the likely root distribution i.e. the presence of hard standing, structures and underground apparatus.
- 3.27 Where groups of trees have been assessed, the Root Protection Area has been shown based on the maximum sized tree in any one group and so may exceed the Root Protection Area required for some of the individual specimens within the group. Further detailed inspection of the individual trees forming a group may be required where development impacts upon the group.
- 3.28 Above ground constraints such as the current crown spread of the trees and an illustration of the shade pattern (where appropriate) have been considered and identified within the Tree Survey Plan and Tree Retention Plan indicates their potential area of shading influence.

Considerations and Limitations of the Tree Survey

- 3.29 The survey was completed from ground level only and from within the boundary of the site. Aerial tree inspections or an assessment of the internal condition of the stem/s or branches were not undertaken at this stage as this level of survey is beyond the scope of the initial assessment.
- 3.30 The statements made in this report regarding defects in assessed trees does not take into account the effects of extreme / adverse weather conditions, changes in land use prior to the site's development, unforeseen accidents or anti-social behaviors, such as vandalism, which occur since the date of the survey. As such, the assessment of tree condition given within applies to the date of survey and cannot be assumed to remain unchanged.

- 3.31 It will be necessary to review all comments and observations made within this report, in accordance with sound arboricultural practice, within two years of the date of survey (unless explicitly stated elsewhere within this report). Further review may also be necessary where site conditions change or works to trees are carried out which have not been specified in detail within this report.
- 3.32 Hedgerows are identified as a Habitat of Principle Importance (HPI) as listed within Section 41 of the Natural Environment and Rural Communities (NERC) Act 2006. The tree survey conducted, in accordance with BS5837, does not assess hedgerows against the Hedgerow Regulations 1997 or specifically from an ecological perspective, and is outside the scope of this assessment.
- 3.33 It may be necessary during detailed design to undertake further assessment and accurate positioning of woody species within tree groups and hedgerows to assist structural calculations for foundation design of structures in accordance with current building regulations. The exact position of individual trees or species included as part of a tree group should be checked and verified on site prior to any decisions for foundation design, tree operations or construction activity being undertaken. Further survey work would be required for calculating foundation depths in accordance with NHBC Chapter 4.2 Building near Trees.

4.0 RESULTS

- 4.1 A total of three individual trees, six groups of trees and a single hedgerow were surveyed as part of the arboricultural assessment. Trees were surveyed as individual trees and groups / blocks of trees where examples are clearly present as such per the description. Refer to– Tree Survey Plan (drawing no. 6158-A-02) and Appendix A – Tree Schedule for full details of the trees included in this assessment.
- 4.2 The table below summarises the trees assessed. Several of the trees indicated on the following table have been discussed in more detail, owing to their physical condition or arboricultural significance.

Results Summary

Table 1: Summary of Trees by Retention Category

	Individual Trees	Total	Groups of Trees	Total
Category U - Unsuitable		0		0
Category A (High Quality / Value)	T3	1		0
Category B (Moderate Quality / Value)	T1, T2	2	G1, G2, G3, G4, G5, G6	6
Category C (Low Quality / Value)		0	H1	1

- 4.3 Tree cover was located mainly around the boundaries of the site or positioned within close proximity as to influence the site and therefore considered for assessment.
- 4.4 The southern boundary of the site was formed by a hedgerow, H1, which comprised common ash *Fraxinus excelsior*, field maple *Acer campestre*, goat willow *Salix caprea*, hawthorn *Crataegus monogyna*, hazel *Corylus avellana*, holly *Ilex aquifolium*, sycamore *Acer pseudoplatanus* and dogwood *Cornus sanguinea*. The hedgerow was also located along the eastern boundary in smaller sections. The hedgerow had been maintained to an approximate height of 2.2m and there were telephone lines running above the crowns toward the western end. Otherwise there were no obvious defects noted. H1 had been assessed as retention category C for its reduced arboricultural quality.
- 4.5 The southern boundary of the smaller field parcel was also formed by G1, a group of common ash which were former coppice stools and had become multi stemmed forms up to 12m in height. The hedgerow, H1, was located underneath the crowns. G1 had been assessed as retention category B for its moderate arboricultural quality.
- 4.6 Within the rear garden of a residential property on the eastern boundary was T1, a semi mature beech *Fagus sylvatica* with three stems, located outside of the site by approximately 0.5m. T1 was considered as having typical form for the species with no obvious defects. T1 has been assessed as retention category B for their moderate arboricultural quality.
- 4.7 The northern boundary was formed by G3, a group of common ash, field maple and hawthorn which formed a dense outgrown hedge with interlocked crowns and dense undergrowth. The site was split by G4, a single species group of hawthorn again forming a dense outgrown hedge with interlocked crowns.
- 4.8 The western boundary was mainly formed by a large tree group G6, with smaller separate pockets of trees in groups, G5 and G7, or as individuals T2 and T3. The main group comprised blackthorn *Prunus spinosa*, crack willow *Salix fragilis*, elder *Sambucus nigra*, field maple, hawthorn, holly, plum *Prunus domestica*, sycamore, dogwood and Wych elm *Ulmus glabra*, and again formed an outgrown hedgerow with hazel coppice stools present and overhead power lines. G5 was a smaller group of common ash, English oak *Quercus robur* and common larch *Larix decidua* up to 14m in height, located approximately 5-7m outside of the site but crowns overhanging the site by up to 4m. G7 was a group of eight field maple, split into two groups which formed collective crowns, with crossing and rubbing branches within the crowns.
- 4.9 T2 was a multi stemmed field maple located between G5 and G7. The crown had been lifted by a flail mower and there were overhead lines to the south west of the crown. T3 was an English oak up to approximately 14m in height, located south of G7 and outside of the site by 1m. There was some minor epicormic growth on the stem but otherwise there were no obvious defects. G3, G4, G5, G6, G7 and T2 had all been assessed as retention category B for their moderate arboricultural quality. T3 had been assessed as retention category A for their good condition, quality, considerable remaining life expectancy by virtue of the species and capability to contribute to the site in the longer term.

Statutory Constraints

- 4.10 Prior to any tree surgery and / or felling of protected trees it will be necessary to apply to the relevant local planning authority to gain consent for the works. For more information regarding Conservation Areas and Tree Preservation Orders it is advised that contact is made with the Local Planning Authority's arboricultural officer, or other such relevant person.

5.0 ARBORICULTURAL IMPACT ASSESSMENT

- 5.1 The following paragraphs present a summary of the tree survey and offers discussion of particular trees and groups recorded in the context of any proposed development in the form of an Arboricultural Impact Assessment in accordance with section 5.4 of BS5837. Any final tree retentions will need to be reconciled with the advice contained within this report.
- 5.2 The AIA has been based upon the Framework Plan and seeks to outline the potential impact that the proposals would have on the existing trees. The above drawing shows proposals which seek to provide a number of residential development parcels serviced by a primary street leading from a proposed vehicle access off Worcester Road along the site's northern boundary.
- 5.3 New green infrastructure provision shall support the scheme and shall provide opportunities for new structured tree and hedgerow planting within areas of open space spanning the southern and south western boundaries. The new tree planting shall include parkland style planting with the aim of supporting and further enhancing the existing tree cover, much of which shall be retained.
- 5.4 The development would also include a flood attenuation basin which would provide an opportunity for new habitat creation and areas of public open space containing a Children's play area.
- 5.5 An overlay of the above layout has been incorporated in the Tree Retention Plan (drwg.no. 6158-A-03C) to assist in identifying potential conflicts with the existing trees.

Arboricultural Implications

- 5.6 Having appraised the above plan for any arboricultural implications that may arise as a result of the layout it would appear that the layout will, through its considerate constraint led design, retain and incorporate the majority of the existing individual and groups of trees by virtue of their positions around the boundaries of the site.
- 5.7 The point of main vehicular access into the site will be forged off the A44 – Worcester Road with the proposals demonstrating a requirement for a new site access via a three arm traffic signal junction with signalised crossing points, along with a 3m wide footway on east side and 2m wide footway on west side.
- 5.8 To facilitate the modifications to the A44 to allow for the access, the existing hedgerow along A44 (G2B); a dense outgrown hedge, shall be removed with new replacement hedgerow planting being positioned to back of kerb as mitigation.

- 5.9 There will also need to be a small section (vehicle link 12m and Pedestrian link 8m) of G3 removed. The loss of a small number of trees forming this group to facilitate the access points should not prove detrimental to the overall tree group, much of which shall be retained.
- 5.1 The implications would be considered acceptable and therefore should not raise any objection from an arboricultural perspective, providing that a sufficient amount and type of replacement tree planting forms part of the supporting landscaping scheme.
- 5.2 The proposals demonstrate that open spaces and green infrastructure provision shall be an integral asset of the proposed scheme and as a result are likely to result in a net gain of tree cover which, as a result, will secure a future generation of tree cover which without the financial investment offered by the development of the site may not have otherwise been provided. The planting of new tree cover would not only benefit the residents of the proposed scheme but also the wider local tree population and this can only be viewed as positive outcome from an Arboricultural perspective.
- 5.3 As the proposals are only in Outline form at present, from an arboricultural perspective and in accordance with the guidance contained within British Standard 5837 (2012), it will be necessary to pay close attention to the layouts of the residential parcels at the appropriate stages in the detailed design process so that the root protection areas of those trees selected for retention can be fully accommodated. This will enable successful integration of the retained specimens into the scheme to ensure their survival in the future.

Tree Management

- 5.4 All retained trees should be subjected to sound arboricultural management as recommended within section 8.8.3 of BS5837 *Post Development Management of Existing Trees*, where there is a potential for public access in order to satisfy the landowner's duty of care. Additionally, inspections annually and following major storms should be carried out by an experienced arboriculturist or arborist to identify any potential public safety risks and to agree remedial works as required.
- 5.5 All tree works undertaken should comply with British Standard 3998:2010 and should therefore be carried out by skilled tree surgeons. It would be recommended that quotations for such work be obtained from Arboricultural Association Approved Contractors as this is the recognised authority for certification of tree work contractors.
- 5.6 All vegetation and, particularly, woody vegetation proposed for clearance should be removed outside of the bird-breeding season (March - September inclusive) as all birds are protected under the Wildlife and Countryside Act, 1981 (as amended) whilst on the nest. Where this is not possible, vegetation should be checked for the presence of nesting birds prior to removal by an experienced ecologist.

6.0 NEW TREE AND HEDGEROW PLANTING

- 6.1 As part of the development proposals an adequate quantity of structured tree planting has been demonstrated predominantly within or close to hard landscaped areas of car parking or alongside the primary access roads within the roadside verges. The purpose and function of this new tree planting should be understood from the start of any design stages so that key objectives from a landscape perspective can also be achieved.

Trees

- 6.2 The landscaping scheme should consider the use of both native tree species (for their low maintenance requirements and nature conservation value) and ornamental species (for their contribution to urban design and amenity value). Species choices should be selected on the basis of their suitability for the final site use. Furthermore, during the design process consultation should be made with the Local Planning Authority to obtain information on their tree strategy and incorporate the planting proposals with any local policies and initiatives and/or Biodiversity Action Plans (BAP).
- 6.3 In line with the NPPF all schemes should aim achieve a net gain in biodiversity value. Nationally recognised biodiversity metrics allow for the inclusion of, not limited to, newly planted scattered trees, woodlands and hedgerows as a means of compensating for loss of habitat as part of the development. Tree and shrub planting can therefore be used to contribute to this biodiversity gain.
- 6.4 To maximise biodiversity value (and contribution to net gain) native species or varieties should be specified. Such provisions can be incorporated into both the hard and soft landscaping of the scheme. It is recommended that tree and hedgerow specifications are made following consultation with guidance published by the Local Planning Authority.
- 6.5 When deciding upon suitable tree species, careful consideration would need to be given to the following: ultimate height and canopy spread, form, habit, density of crown, potential shading effect, colour, water demand, soil type and maintenance requirements in relation to both the built form of the new development and existing properties.
- 6.6 Through careful species selection, the landscape scheme shall reduce the risk of trees being removed in the future on the grounds of nuisance. Nuisance can be perceived in a number of ways and vary from person to person however most commonly, within the context of trees, low overhanging branches, excessive shading, seasonal leaf fall and the misinformed perception that trees close to buildings cause damage.

Hedgerows

- 6.7 Hedgerows are identified as a Habitat of Principle Importance (HPI) as listed within Section 41 of the Natural Environment and Rural Communities (NERC) Act 2006. Consequently, it is important that the proposed scheme delivers a net gain in terms of linear hedgerows through new planting to compensate for any losses. Species should be native, and characteristic of the locality.
- 6.8 Recommended species for native hedgerow planting are as follows:

- *Crataegus monogyna*
- *Prunus spinosa*
- *Cornus sanguinea*
- *Corylus avellana*
- *Acer campestre*
- *Euonymus europaeus*

Rooting Environment and Soil Volumes

- 6.9 The success of any landscaping scheme relies on an adequate provision of a high-quality rooting environment within which trees can thrive and reach their full potential. Planting trees with due care and consideration can, in the long term, provide a greater return on a schemes green investment and ensure trees remain healthy and grow to mature proportions. Healthy mature trees integrate well into the built environment; increase the maturity of the landscape; help provide a natural green and leafy urban environment in which people would want to reside whilst also benefiting local wildlife.
- 6.10 The planting of trees within confined urban environments should consider the use of appropriately designed planting pits specifically engineered to promote tree health and longevity. Crucially the aim will be to provide an adequate volume of quality soil for roots to suitably develop by calculating the amount of available soil volumes needed and selecting species whose mature size is compatible with the site. This is an integral component of the planning stage (Lindsey & Bassuk, 1991).
- 6.11 In a natural environment free from constraints to growth, it has been proven through research that root systems can extend up to three times the radius of the tree crown and although in an urban environment there is often insufficient space to accommodate the extent of the full potential for root growth, all efforts should be made to at least provide as much soil volume as possible. One researched method of calculating the minimum required soil volume is as follows:

Table 4: Example of calculating Soil Volume for New Tree Planting (Source: CIRIA C712 and Calculating Target Soil Volumes – Green Blue Urban)

Projected canopy area of mature tree (m) x depth 0.6m		
Calculation 1	Projected mature canopy diameter (metres)	= 3 (Diameter)
Calculation 2	Projected mature canopy area (square metres), ($n \times \text{Radius}^2$)	= 7.1 (Area)
Calculation 3	Target soil volume (cubic metres), (Area x 0.6m)	= 4.24 (Volume)
	Target soil volume	= 4.24m ³

General Planting Recommendations

- 6.12 Wherever possible, following discussions with the developer and utility companies, common service trenches should be specified to minimise land take associated with underground service provision and facilitation access for future maintenance.

- 6.13 Tree planting should be avoided where they may obstruct overhead power lines or cables. Any underground apparatus should be ducted or otherwise protected at the time of construction to enable trees to be planted without resulting in future conflicts.

General Design Principles in Relation to Retained Trees

- 6.14 As recommended by the guidance given in section 7.7 of BS5837 services, where possible, should not encroach within the Root Protection Areas of retained trees. If below-ground services are proposed within a Root Protection Area, modifications to the alignment of the service route may need to be made in order to minimise adverse effects on root stability and overall tree health.
- 6.15 Consideration may also need to be given to the potential for tree roots of newly planted trees and hedgerows to affect or compromise the future services. As far as feasible, it would be preferable that proposed services near both the existing and any new planting should be ducted for ease of access and maintenance and grouped together to minimise any future disturbance.

7.0 TREE PROTECTION MEASURES

- 7.1 Retained trees will be adequately protected during works ensuring that the calculated root protection area for all retained trees can be appropriately protected through the erection of the requisite tree protection barriers. Measures to protect trees should follow the guidance in BS5837 and will be applied where necessary for the purpose of protecting trees within the site whilst allowing sufficient access for the implementation of the proposed layout. These have been broadly summarised below.

General Information and Recommendations

- 7.2 All trees retained on site will be protected by suitable barriers or ground protection measures around the calculated RPA, crown spread of the tree or other defined constraints of this assessment as detailed by section 6 and 7 of BS5837.
- 7.3 Barriers will be erected prior to commencement of any construction work and before demolition including erection of any temporary structures. Once installed, the area protected by fencing or other barriers will be regarded as a construction exclusion zone. Fencing and barriers will not be removed or altered without prior consultation with the Project Arboriculturist.
- 7.4 Any trees that are not to be retained as part of the proposals should be felled prior to the erection of protective barriers. Particular attention needs to be given by site contractors to minimise damage or disturbance to retained specimens.
- 7.5 Where it has been agreed, construction access may take place within the root protection area if suitable ground protection measures are in place. This may comprise single scaffold boards over a compressible layer laid onto a geo-textile membrane for pedestrian movements. Vehicular movements over the root protection area will require the calculation of expected loading and the use of proprietary protection systems.
- 7.6 Confirmation that tree protective fencing or other barriers have been set out correctly should be gained prior to the commencement of site activity.

Tree Protection Barriers

- 7.7 Tree protection fencing should be fit for the purpose of excluding any type of construction activity and suitable for the degree and proximity of works to retained trees. Barriers must be maintained to ensure that they remain rigid and complete for the duration of construction activities on site.
- 7.8 In most situations, fencing should comprise typical construction fencing panels attached to scaffold poles driven vertically into the ground. For particular areas where construction activity is anticipated to be of a more intense nature, supporting struts, acting as a brace should be added and fixed into position through the application of metal pins driven into the ground to offer additional resistance against impacts.
- 7.9 Where site circumstances and the risk to retained trees do not necessitate the default level of protection an alternative will be specified appropriate to the level / nature of anticipated construction activity. The recommended methods of fencing specifications for this site have been illustrated in Appendix B.
- 7.10 It may be appropriate on some sites to use temporary site offices, hoardings and lower level barrier protection as components of the tree protection barriers. Details of the specific protection barriers for the site can be provided should the application be approved, as part of a site specific Arboricultural Method Statement for a Reserved Matters application and in accordance with the guidance contained within BS5837.

Protection outside the exclusion zone


- 7.11 Once the areas around trees have been protected by the barriers, any works on the remaining site area may be commenced providing activities do not impinge on protected areas.
- 7.12 All weather notices should be attached to the protective fencing to indicate that construction activities are not permitted within the fenced area. The area within the protective barriers will then remain a construction exclusion zone throughout the duration of the construction phase of the proposed development. Protection fencing signs can be provided upon request.
- 7.13 Wide or tall loads etc should not come into contact with retained trees. Banksman should supervise transit of vehicles where they are in close proximity to retained trees.
- 7.14 Oil, bitumen, cement or other material that is potentially injurious to trees should not be stacked or discharged within 10m of a tree stem. No concrete should be mixed within 10m of a tree. Allowance should be made for the slope of ground to prevent materials running towards the tree.
- 7.15 No fires will be lit where flames are anticipated to extend to within 5m of tree foliage, branches or trunk, taking into consideration wind direction and size of fire.
- 7.16 Notice boards, telephone cables or other services should not be attached to any part of a retained tree.
- 7.17 Any trees which need to be felled adjacent to or are present within a continuous canopy of retained trees, must be removed with due care (it may be necessary to remove such trees in sections).

Protection of Trees Close to the Site

- 7.18 A number of trees were located on the boundaries of the site and therefore the root protection area and crown spread of these trees will need to be protected in the same way as all the retained trees within the site. All trees located outside the boundaries of the assessment site yet within close proximity to works should be adequately protected during the course of the development by barriers or ground protection around the calculated root protection area.
- 7.19 Any trees which are to be retained and whose Root Protection Areas may be affected by the development should be monitored, during and after construction, to identify any alterations in quality with time and to assess and undertake any remedial works required as a result.

Protection for Aerial Parts of Retained Trees

- 7.20 Where it is deemed necessary to operate wide or tall plant within close proximity to trees it is best advised that appropriate, but limited tree surgery, be carried out beforehand to remove any obstructive branches as any such equipment would have potential to cause damage to parts of the crown material, i.e. low branches and limbs, of retained trees within the protective barriers. This is termed as 'access facilitation pruning' within BS5837. Any such pruning should be undertaken in accordance with a specification prepared by an arboriculturist.
- 7.21 A pre-commencement site meeting with contractors who are responsible for operating machinery is advised to firstly highlight the potential for damage occurring to tree crowns and to ensure that extra care is applied when manoeuvring machinery during such operations within close proximity to retained trees to avoid any contact.
- 7.22 In the event of having caused any branch or limb damage to retained trees it is strongly recommended that suitable tree surgery be carried out, in accordance with British Standard 3998:2010 and in agreement with the Local Planning Authority prior to correcting the damage, upon completion of development.



KEY

Category U - Unsuitable for Retention
(BS 5837:2012)

Category A - Trees of High Quality
(BS 5837:2012)

Category B - Trees of Moderate Quality
(BS 5837:2012)

Category C - Trees of Low Quality
(BS 5837:2012)

Group hatching
(Colour indicates BS Category)

Hedgerow hatching
(Colour indicates BS Category)

Root Protection Area (the RPA has been altered
where appropriate to reflect underground constraints)

Individual / Group Number and BS Category

Indicative Shade Pattern (where appropriate)

N

Scale 1:1000 @ A3

0 25 50m

NOTES

All dimensions to be verified on site. Do not scale this drawing. All discrepancies to be clarified with project Arboriculturalist. Drawing to be read in conjunction with Arboricultural Assessment and Appendix A - Tree Schedule.

Drawing produced in colour, a monochrome copy should not be relied upon, and is based on digital information supplied by the client in dwg format. The exact position of trees are to be checked and verified on site prior to any tree work or construction work being undertaken.

Trees are living organisms that change over time, the condition of all trees illustrated herein, are to be checked by a qualified arboriculturalist or tree surgeon should works commence 12 months after the time of this survey. Please note that no works should be undertaken to any trees illustrated herein without first obtaining the proper authorisation to do so.

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.

Ordnance Survey material is used with the permission of The Controller of HMSO, Crown copyright 100018896.

rev	date	description	by
-	08.08.2016	First Issue	CTT

masterplanning

environmental assessment

landscape design

urban design

ecology

architecture

arboriculture

FPCR Environment and Design Ltd
Lockington Hall
Lockington
Derby DE74 2RH

t: 01509 672772

f: 01509 674565

e: mail@fpcr.co.uk

w: www.fpcr.co.uk

client
Gladman Developments Limited

project
Pencombe Lane
Bromyard

drawing title
TREE SURVEY PLAN

scale
1:1000 @ A3

drawn
CTT

date
August 2016

drawing number
6158-A-02

rev
-

CAD file: \\Fpcr-vm-04\projects\6100\6158\ARB\2nd Application\Fig 2 Tree Survey Plan.dwg



KEY



Tree/Group to be Retained



Tree/Group to be removed to facilitate the proposals



Category U - Unsuitable for retention on arboricultural grounds



Hedgerow Proposed to be Retained and Incorporated into the New Development



Hedgerow Proposed to be Removed to Facilitate
the Development upon Approval of the Application



Root Protection Area
(Shown for retained trees only)




Individual / Group Number and BS Category



Indicative Shade Pattern (where appropriate)



Scale 1:1000 @ A3



NOTES

All dimensions to be verified on site. Do not scale this drawing. All discrepancies to be clarified with project Arboriculturalist. Drawing to be read in conjunction with Arboricultural Assessment and Appendix A - Tree Schedule.

Drawing produced in colour, a monochrome copy should not be relied upon, and is based on digital information supplied by the client in dwg format. The exact position of trees are to be checked and verified on site prior to any tree work or construction work being undertaken.

Trees are living organisms that change over time, the condition of all trees illustrated herein, are to be checked by a qualified arboriculturalist or tree surgeon should works commence 12 months after the time of this survey. Please note that no works should be undertaken to any trees illustrated herein without first obtaining the proper authorisation to do so.

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part without written consent of FPCR Environment and Design Ltd.

Ordnance Survey material is used with the permission of The Controller of HMSO, Crown copyright 100018896.

-	17.06.2014	First Issue	TJF
A	19.08.2016	New Framework Inserted	CT
B	09.10.2018	Revised Framework Inserted	CT
C	08.08.2019	Revised Framework Inserted	EC

rev	date	description	by
-----	------	-------------	----



- masterplanning ■
- environmental assessment ■
- landscape design ■
- urban design ■ FPCR Environment and Design Ltd
- ecology ■ Lockington Hall
- architecture ■ Lockington
- arboriculture ■ Derby DF74 2RH

t: 01509 672772
f: 01509 674565
e: mail@fpcr.co.uk
w: www.fpcr.co.uk

client
Gladman Developments Limited

project
**Pencombe Lane
Bromyard**

drawing title
TREE RETENTION PLAN

scale
1:1000 @ A3

drawn/checked
EC / CTT

date
August 2019

drawing number

6158-A-03

rev

C

CAD file: \\Fpcr-vm-04\projects\6100\6158\ARB\2018\Plans\6158-A-03 Tree Retention Plan.dwg

Appendix A - Tree Schedule

Measurements	Age Class	Overall Condition	Root Protection Area (RPA)
Height - Measured using a digital laser clinometer (m)	YNG: Young trees up to ten years of age	G - Good: Trees with only a few minor defects and in good overall health needing little, if any attention	<ul style="list-style-type: none">• The RPA Radius column provides the extent of an equivalent circle from the centre of the stem (m).• The RPA is calculated using the formulae described in paragraph 4.6.1 of British Standard 5837: 2012 and is indicative of the rooting area required for a tree to be successfully retained. Tree roots extend beyond the calculated RPA in many cases and where possible a greater distance should be protected.• Where veteran trees have been identified the RPA has been calculated in accordance with Natural England guidance i.e. 15x the stem diameter, uncapped.
Stem Dia. - Diameter measured (mm) in accordance with Annex C of the BS5837	SM: Semi-mature trees less than 1/3 life expectancy	F - Fair: Trees with minor rectifiable defects or in the early stages of stress from which it may recover	
Crown Radius - Measured using a digital laser clinometer radially from the main stem (m)	EM: Early mature trees 1/3 – 2/3 life expectancy	P - Poor: Trees with major structural and/or physiological defects such that it is unlikely the tree will recover in the long term	
Abbreviations est - Estimated stem diameter avg - Average stem diameter for multiple stems upto - Maximum stem diameter of a group	M: Mature trees over 2/3 life expectancy	D - Dead: This could also apply to trees in an advanced state of decline and unlikely to recover	
	OM: Over mature declining or moribund trees of low vigour	The BS category particular consideration has been given to the following <ul style="list-style-type: none">• The health, vigour and condition of each tree• The presence of any structural defects in each tree/group and its future life expectancy• The size and form of each tree/group and its suitability within the context of a proposed development• The location of each tree relative to existing site features e.g. its screening value or landscape features• Age class and life expectancy	
	V: Veteran tree possessing certain attributes relating to veteran trees		

Structural Condition
<p>The following is an example of considerations when inspecting structural condition:</p> <ul style="list-style-type: none"> The presence of fungal fruiting bodies around the base of the tree or on the stem, as they could possibly indicate the presence of possible internal decay Soil cracks and any heaving of the soil around the base Any abrupt bends in branches and limbs resulting from past pruning Tight or weak 'V' shaped forks and co-dominant stems Hazard beam formations and other such biomechanical related defects (as described by Claus Mattheck, Body Language of Trees HMSO Research for Amenity Trees No. 4 1994) Cavities as a result of limb losses or past pruning Broken branches or storm damage Damage to roots Basal, stem or branch / limb cavities Crown die-back or abnormal foliage size and colour


Quality Assessment of BS Category
Category U - Trees in such a condition that they cannot realistically be retained as living trees in the context of the current land use for longer than 10 years.
Category A - Trees of high quality with an estimated remaining life expectancy of at least 40 years.
Category B - Trees of moderate quality with an estimated remaining life expectancy of at least 20 years.
Category C - Trees of low quality with an estimated remaining life expectancy of at least 10 years, or young trees with a stem diameter below 150mm.
Sub-categories: (i) - Mainly arboricultural value (ii) - Mainly landscape value (iii) - Mainly cultural or conservation value

Appendix Summary

	Individual Trees	Totals	Tree Groups and Hedgerows	Totals
Category U		0		0
Category A	T3	1		0
Category B	T1, T2	2	G1, G2, G3, G4, G5, G6	6
Category C		0	H1	1
Total		3	Total	7

BS Category Tree Type Distribution displays the proportion of trees assessed in each type to enable a better understanding of the category distribution.

Age Distribution of Tree Stock shows the number of trees in each age category across the tree stock allowing assessment of their longevity to be made.




Tree No	Species	Height	Stem Dia.	Crown Radius	Age Class	Overall Condition	Structural Condition	RPA	RPA Radius	BS5837 Cat
INDIVIDUAL TREES										
T1	Beech Fagus sylvatica	8	120 150 180	2	SM	F	Off site by 0.5m Typical form with no major defects	31	3.2	B (i)
T2	Field Maple Acer campestre	8	100 90 120 150 200	3.5	EM	G	Overhead lines to the south west Lifted crown by flail mower Within TG6	43	3.7	B (i)
T3	English Oak Quercus robur	14	est 750	9	M	G	Off site by 1m No obvious defects Minor epicormic growth	254	9.0	A (i)

Group No	Species	Height	Stem Dia.	Crown Radius	Age Class	Overall Condition	Structural Condition	RPA	RPA Radius	BS5837 Cat
GROUPS OF TREES										
G1	Common Ash Fraxinus excelsior	12	6x180	3.5	SM	F	Former coppice stools Hedgerow beneath	88	5.3	B (ii)
G2	Common Ash Fraxinus excelsior Field Maple Acer campestre Hawthorn Crataegus monogyna	8	150	3.5	M	G	Dense outgrown hedge Interlocked crowns Dense undergrowth Typical forms for the species with no obvious defects	10	1.8	B (ii)
G3	Hawthorn Crataegus monogyna	4	6x50	2.5	EM	G	Dense interlocked forms Single species planted hedgerow	7	1.5	B (ii)
G4	Common Ash Fraxinus excelsior English Oak Quercus robur Common Larch Larix decidua	14	400	8	SM/EM	G	Off site group between 5-7metres from the boundary Overhanging site by 4m	72	4.8	B (ii)


Group No	Species	Height	Stem Dia.	Crown Radius	Age Class	Overall Condition	Structural Condition	RPA	RPA Radius	BS5837 Cat
G5	Blackthorn Prunus spinosa Crack Willow Salix fragilis Elder Sambucus nigra Field Maple Acer campestre Hawthorn Crataegus monogyna Holly Ilex aquifolium Plum Prunus domestica Sycamore Acer pseudoplatanus Dogwood Cornus sanguinea Wych Elm Ulmus glabra	8	200	4	SM/M	G	Outgrown hedgerow Hazel coppice stools present Blackthorn spread into the field Beneath over head power lines	18	2.4	B (ii)
G6	Field Maple Acer campestre	14	350	6	EM	G	Eight specimens forming one collective crown in two groups Crossing and rubbing branches Tall for the species with unusual forms	55	4.2	B (ii)

Hedge No	Species	Height	Stem Dia.	Crown Radius	Age Class	Overall Condition	Structural Condition	RPA	RPA Radius	BS5837 Cat
HEDGEROWS										
H1	Common Ash Fraxinus excelsior Field Maple Acer campestre Goat Willow Salix caprea Hawthorn Crataegus monogyna Hazel Corylus avellana Holly Ilex aquifolium Sycamore Acer pseudoplatanus Dogwood Cornus sanguinea	2.2	6x50	1.5	SM/M	F	Self set forms Maintained hedgerow Telephone lines above the crown	7	1.5	C (ii)



Standard specification for protective barrier

1. Standard scaffold poles
2. Heavy gauge 2m tall galvanized tube and welded mesh infill panels
3. Panels secured to scaffold frame with wire ties
4. Ground level
5. Uprights driven into the ground until secure (min depth of 0.6m)
6. Standard scaffold clamps
7. Construction Exclusion Zone signs



Above ground stabilising systems

1. Stabiliser strut with base plate secured with ground pins
2. Feet blocks secured with ground pins
3. Construction Exclusion Zone signs

NOTES

This drawing is the property of FPCR Environment and Design Ltd and is issued on the condition it is not reproduced, retained or disclosed to any unauthorised person, either wholly or in part with written consent of FPCR Environment and Design Ltd.



masterplanning ■
 environmental assessment ■
 landscape design ■
 urban design ■ FPCR Environment and Design Ltd
 ecology ■ Lockington Hall
 architecture ■ Lockington
 arboriculture ■ Derby DE74 2RH

t: 01509 672772
 f: 01509 674565
 e: mail@fpcr.co.uk
 w: www.fpcr.co.uk

drawing title

APPENDIX B PROTECTIVE FENCING SPECIFICATIONS

CAD file: S:\Arb resources\Basic Templates\Tree Protection\Appendix B - Protective Fencing A4.dwg