



Rev.	Description.	Date.

Abbreviations			
a/c	Air Conditioning	g	Gully
b	Bollard	bt	British Telecom Cover
boe	Brick on Edge Coping	gv	Gas Valve
bt	British Telecom Cover	ht	Height
catv	Cable TV Cover	ic	Inspection Cover
c/b	Close Board	il	Invert Level
cf	Ceiling Fall	l/a	Limited Access
cl	Cover Level	l/v/a	Limited Visual Access
conc	Concrete	rad	Radiator
fai	Fresh Air Inlet	rwp	Rain Water Pipe
far	Flat Asphalt Roof	svp	Soil & Vent Pipe
f/c	False Ceiling	utl	Unable To Lift
fhr	Fire Hose Reel	whb	Wash Hand Basin

Legend	
-----	Indicates overhead or hidden feature.
- . - . -	Indicates centre of steel , handrail or as annotated.
dh. 1960	Door height from finished floor level. (mm)
c. 950	Cill height from finished floor level. (mm)
h. 1380	Head height from cill level. (mm)
sp. 2250	Spring height from cill or finished floor level. (mm)
(2550)	Height to ceiling/beam/soffit. (mm)
Trees identified and measured approximately only	
Tree species	
d. 0.5m -	Trunk diameter in metres
h. 8m -	Height in metres
s. 10m -	Spread in metres

Please Note:	
1)	This survey has been produced in accordance with the RICS specifications for Surveys of Land, Buildings and Utility Services.
2)	The accuracy of this survey is dependent upon the scale of the commissioned survey. Users must be careful when re-scaling from any plots, using the grid to verify the scale.
3)	This survey is on the OS grid fixed using the OSTN15 model via GPS.

Levels	
All levels are Above Ordnance Datum, fixed to the OS Network by GPS. Using GPS Active Network and transformed using the OSTN15 model.	
All level positions are indicated by a cross or as noted.	

Project Title:	Huts at Hope Lodge		
Project No.:	2712		
Drawing Title:	Part Site Plan with OS extract		
Drawing No.:	2712-02	Revision:	
Client:	Mr A Tilbury		
Drawn:	S.H.	Checked:	R.H.
Scale:	1:100	Sheet Size:	A2
Date:	July 2024		



Orbis Surveys

Land and Measured Building Services

email: orbissurveysuk@gmail.com
telephone: 07411446252