New Build Kitchen Extension at The VAGA, Ganarew, Wyastone Leys Estate, Monmouth

Foul and Stormwater Drainage Strategy.

30th November 2020.



New Build Kitchen Extension at The VAGA, Ganarew, Wyastone Leys Estate, Monmouth

Foul and Stormwater Drainage Strategy.

30th November 2020.

This report considers the particular instructions and requirements of our client.

It is not intended for and should not be relied upon by any third party and no responsibility is undertaken to any third party

Document Verification





ob title		New Build Kitchen Extension at The VAGA, Ganarew, Wyastone Leys Estate, Monmouth			Job number				
		,	2019_046						
Document title		Foul and Sto							
_	_								
Document re	f 								
Revision	Date	Filename	2019_046/30_11_2020						
)1	16/06/2021	Description	Final Issue	Final Issue					
			Prepared by	Checked by	Approved by				
		Name	Eugene Travers Jones	Eugene Travers Jones	Eugene Travers Jones				
				Issue Document Veri	fication with Document				

Contents

1.	Introduction.	1
2.	The Predevelopment Situation.	2
3.	Existing and Future Foul Discharge.	3
4.	Existing and Future Stormwater Discharge.	4
5.	Implementation.	6
6.	Management and Maintenance.	7
Append	lix A	
Append	lix B	

1. Introduction.

Andrew O'Sullivan is proposing to extend his current property by building a mono-pitched single storey kitchen dining space immediately adjacent to the existing northern elevation of the existing dwelling.

The new extension is some 36 m² in plan area and will be constructed on an existing yard area that is currently finished mainly with chippings.

The other remaining rooms (lounge, dining rooms, bathrooms, and bedroom will remain as currently is, there will be no increase in occupancy as a result of the proposals.

WL Squared have been engaged to consider implications of the proposals on the existing drainage systems and make recommendations as to any revisions that may be required to the existing drainage system serving the property or in relation to any new drainage systems that will be needed to serve the property as a result of the proposed extension being developed.

This document describes the considerations given and the conclusions of those considerations including providing outline details of any new drainage systems required.

2. The Predevelopment Situation.

The existing property at the VAGA is a detached four-bedroom house, with numerous outbuildings including a barn, a forecourt area and a large landscaped area to the east alongside the Rover Wye.

The site location is shown below.



The property currently occupying the site is served by a private foul drainage system that utilises a standalone package treatment plant.

The stormwater run-off from the hard surfacing with the site is collected locally and discharged (as is typical with some many older rural properties) directly into the ground. This run-off will ultimately make its way into the adjacent River Wye.

3. Existing and Future Foul Discharge.

There is no change in foul flows discharged from the property as a result of the development proposals. Hence, there is no requirement for any changes to the foul drainage system serving the site.

The new kitchen will be connected into the existing foul drainage system serving the existing property.

4. Existing and Future Stormwater Discharge.

The discharge of stormwater falling on the existing property will remain unchanged as a result of the proposals, whilst the new extension (some 36m² of hard area) will be provided with a new separate drainage system.

The new extension is provided with a mono-pitch roof which falls to a linear gutter. Rainwater falling on the roof will be collected by the roof/gutter system and discharged from the roof via a rainwater pipe into a suitably planted feature water garden constructed alongside the new extension, similar to that shown below.



Rainwater will be filtered by the water garden prior to its discharge via a small network of underground pipework into a soakaway. Drawings of the proposed system are provided within Appendix A.

The pipework network and soakaway is designed to cater for all the run-off from the new roof area in a 1 in 100 year storm event taking account of a 30% increase in flow resulting from climate change. The network will be provided with a catchpit to catch silt deposits and an inspection hatch with the soakaway itself to aid maintenance. See Appendix B.

British Geological Survey (BGS) 1:50,000 maps have been used to determine that the underlying subsoils within the area comprise of clayey sands and gravels and a typical likely permeability value for such soils has been used when calculating the size of the soakaway for schematic design purposes. Filtration testing

will be undertaken on site at the position of the proposed soakaway and this information used to re-size the soakaway once the technical design stage progresses and before construction starts.

Rainwater harvesting and re-use was been considered but rejected as this is impractical as it would require the complete re-plumbing of the existing house.

P:\PROJECTS\2019_046 WL Squared Ltd
November 2020

5. Implementation.

The drainage systems described will be constructed as part of the proposed development, they will become operable as they are completed.


6. Management and Maintenance.

Accessible catchpit inspection chambers have been incorporated as part of the attenuation system, upstream of the soakaway. The catchpit inspection chambers will minimise the volume of silts and debris entering the soakaway and therefore will require six monthly checks for blockages and cleaned out as necessary.

The planting within the rainwater garden will be maintained properly on an ongoing basis the nature of the maintenance will be undertaken to suit the species of planting used. The raingarden will be reconstructed/replanted every 10 years.

No other specific maintenance requirements are necessary.

Appendix A



TYPICAL DETAIL POLYSTORM CONNECTORS

ELEVATION

(Scale 1:10)

- 2. ALL BUILDING DRAINAGE TO BE INSTALLED AND TESTED IN COMPLIANCE WITH THE BUILDING REGULATIONS 2000 DRAINAGE AND WASTE DISPOSAL APPROVED DOCUMENT H 2002 EDITION.
- ALL COMPONENTS AND MATERIALS ARE TO BE MANUFACTURED AND SUPPLIED IN ACCORDANCE WITH THE RELEVANT BRITISH STANDARDS, AND LAID AND BACKFILLED IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS AND
- . THE CONTRACTOR SHALL, BEFORE COMMENCING THE WORKS, VERIFY ALL SITE AND SETTING DIMENSIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE TRUE AND PROPER SETTING OUT OF THE WORKS AND FOR THE CORRECTNESS OF THE POSITIONS, LEVELS, DIMENSIONS, AND ALIGNMENT
- SMALL LIGHTWEIGHT ACCESS COVERS SHOULD BE SECURED) WITH SCREWS TO
- 6. ALL INSITU CONCRETE USED TOR DRAINAGE WORKS SHALL BE GEN1 C20 MIX AND COMPLY WITH BS EN 206-1 AND
- THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELATED WL2, ARCHITECTS & SUB-CONTRACTORS DRAWINGS. IN THE CASE OF DISCREPANCIES BETWEEN DRAWING
- 8. THIS DRAWING TO BE READ IN CONJUNCTION WITH WL 2 DRAWINGS D001

STORMWATER SYSTEM



2019 046

CONSULTING CIVIL AND STRUCTURAL ENGINEERS 47 Park Street Bridgend, CF31 4AX Telephone: 01656 669867

Scales AS SHOWN Originator IA 01/02/2020

Appendix B



WL Squared Ltd. 47 Park Street Bridgend

CF31 4AX

THE VAGA, Ganarew, Wyastone Leys Estate, Monmout							
	Calcs for						
	Soakaway Serving New Extension						

ETJ

27/11/2020

2019.046

naga na /Bayisian

Start page no./Revision

ETJ

Job no.

Soakaway Serving New Extension 1

Calcs date Checked by Checked date Approved by Approved date

27/11/2020

SOAKAWAY DESIGN

In accordance with BRE Digest 365 - Soakaway design

Tedds calculation version 2.0.04

27/11/2020

Design rainfall intensity

Project

Calcs by

ETJ

Ratio 60 min to 2 day rainfall of 5 yr return period r = **0.350**

5-year return period rainfall of 60 minutes duration M5_60min = **19.0** mm

Increase of rainfall intensity due to global warming pclimate = 30 %

Soakaway / infiltration trench details

Soakaway type Rectangular

Minimum depth of pit (below incoming invert) d = 1000 mmWidth of pit w = 1000 mmLength of pit l = 2423 mmPercentage free volume $V_{\text{free}} = 95 \%$ Soil infiltration rate $f = 7.00 \times 10^{-6} \text{ m/s}$

Wetted area of pit 50% full $a_{s50} = I \times d + w \times d = 3422847 \text{ mm}^2$

Table equations

Inflow (cl.3.3.1) I = M100 \times A Outflow (cl.3.3.2) O = $a_{s50} \times f \times D$ Storage (cl.3.3.3) S = I - O

Duration, D (min)	Growth factor Z1	M5 rainfalls (mm)	Growth factor Z2	100 year rainfall, M100 (mm)	Inflow (m³)	Outflow (m³)	Storage required (m³)
5	0.36;	8.8;	1.88;	16.6;	0.60;	0.01;	0.59
10	0.51;	12.5;	1.95;	24.4;	0.88;	0.01;	0.86
15	0.62;	15.2;	1.99;	30.3;	1.09;	0.02;	1.07
30	0.79;	19.4;	2.03;	39.4;	1.42;	0.04;	1.37
60	1.00;	24.7;	2.01;	49.7;	1.79;	0.09;	1.70
120	1.22;	30.2;	1.97;	59.5;	2.14;	0.17;	1.97
240	1.50;	37.0;	1.91;	70.8;	2.55;	0.35;	2.20
360	1.69;	41.7;	1.88;	78.3;	2.82;	0.52;	2.30
600	1.95;	48.1;	1.83;	87.8;	3.16;	0.86;	2.30
1440	2.48;	61.3;	1.73;	106.2;	3.82;	2.07;	1.75

Required storage volume

 $S_{req} = 2.30 \text{ m}^3$

Soakaway storage volume $S_{act} = I \times d \times w \times V_{free} = 2.30 \text{ m}^3$

PASS - Soakaway storage volume

Time for emptying soakaway to half volume $t_{s50} = S_{req} \times 0.5 / (a_{s50} \times f) = 13hr \ 19min \ 57s$

PASS - Soakaway discharge time less than or equal to 24 hours