


PLANTING SCHEDULE



- A** MIXED NATIVE SHRUB PLANTING, INC:
- NET-VEINED WILLOW (SALIX RETICULATA) 40%
  - BUTCHER'S BROOM (RUSCUS ACULEATUS) 20%
  - COMMON BROOM (CYTISUS SCOPARIUS) 20%
  - DOWNY WILLOW SALIX LAPPONUM) 20%
  - (20-40CM SPACING WITH 5-30CM PLANTING SIZE)
- B** INCLUDING INTERSPERSED BULB PLANTING:
- SELECTION OF, CROCUS, TULIP, SNAKES HEAD, DAFFODIL, LILY OF THE VALLEY, PUSCHKINIA, SNOW DROPS, COLCHICUMS. MIXTURE OF EVERGREENS, AQUILEGIA, HELLEBORES, ASTILBE CHINENSIS, LILUM, AGAPANTHUS, HOSTA'S, HYDRANGEA, HAKONECHLOA. (20-60CM SPACING WITH 5-30CM PLANTING SIZE)
- C** ACERS, PEONIES, DAPHNE, EVERGREEN SHRUBS (20-40CM SPACING WITH 5-30CM PLANTING SIZE)
- D** AZALEAS, HOLLYHOCKS, ANEMONES, LILAC, CLEMATIS, QUEEN ANNE LACE, EVERGREEN SHRUBS (20-40CM SPACING WITH 5-30CM PLANTING SIZE)

- AC** COMMON NAME - FIELD MAPLE NAME- ACER CAMPESTRE HEIGHT- 125-150CM SPECIFICATION - 2X: FEATHERED: 5 BREAKS: BR
- CC** COMMON NAME - COCKSPUR THORN NAME- CRATAEGUS CRUSGALLI HEIGHT- 80-100CM SPECIFICATION - TRANSPLANT: BRANCHED: 3 BREAKS: BR
- PA** COMMON NAME - WILD CHERRY NAME- PRUNUS AVIUM HEIGHT- 125-150CM SPECIFICATION - 2X: FEATHERED: 5 BREAKS: BR

- PLANTING & ESTABLISHING OF GARDEN:
- PLANTING TO BE UNDERTAKEN BEFORE THE END OF THE FIRST AVAILABLE PLANTING SEASON
  - FOLLOWING COMPLETION OF THE DWELLING.
- AREAS OF LAWN:
- TOPSOIL LOOSENED TO 300MM, SURFACE STONES (+10MM) & DEBRIS REMOVED.
  - LOW POINTS & HOLLOWES FILLED, SURFACE RAKED TO UNIFORM FRIABLE FINISH
  - SEED RATE APPLIED TO 30-50G/M2, WITH THE REQUIRED QUANTITY SPLIT IN TWO AND APPLIED AT RIGHT ANGLES TO EACHOTHER.
  - TO BE IRRIGATED TO A DEPTH OF 100MM REGULARLY, AS SITE & WEATHER CONDITIONS REQUIRE
- AMENITY PLANTING:
- PREPARE SOIL AS SPECIFIED ABOVE, APPROPRIATE TO THE SITE. ENSURE THAT ALL VISIBLE ROOTS AND LARGE STONES WITH A DIAMETER GREATER THAN 50 MM ARE REMOVED. SPREAD SANITIZED IMPORTED GREEN WASTE AND STABILIZED COMPOSTS AT 7.5M<sup>3</sup>/100 M<sup>2</sup> (75MM DEPTH OVER PLANTING AREA). INCORPORATE INTO THE TOP 200MM OF THE SOIL USING A ROTARY CULTIVATOR OR BY MANUAL MEANS
  - APPLY PRE-APPROVED CONTROLLED RELEASE (8-9 MONTHS) PLANTING FERTILISER 11-21-9+6MGO AT THE MANUFACTURERS RECOMMENDED RATES AND INCORPORATED INTO THE TOP 150MM OF THE SOIL PRIOR SETTING OUT AND PLANTING.
  - BARE ROOT AND CONTAINER GROWN DECIDUOUS SHRUBS: LATE OCTOBER TO LATE MARCH.
  - ROOT BALLED AND CONTAINER GROWN EVERGREENS: SEPTEMBER/ OCTOBER OR APRIL/ MAY.
  - CONTAINER GROWN PLANTS CAN BE PLANTED AT OTHER TIMES ONLY IF ADEQUATE IRRIGATION CAN BE PROVIDED

- DRIVEWAY BUILD-
- 14-20MM DECORATIVE LOOSE GRAVEL- NEEDINGWORTH STONE- PERMEABLE 150MM CONSOLIDATED TYPE 3 MOT HARDCORE (DTp3) (REDUCED FINES PERMEABLE SUB-BASE) CONSOLIDATION & SPECIFIC DEPTH TO BE CONFIRMED TO SUIT SITE CONDITIONS



 OAKWRIGHTS®	T.J. CRUMP OAKWRIGHTS LTD THE LAKES, SWAINSHILL, HEREFORD, HR4 7PU  T: (01432) 353353 E: enquiries@oakwrights.co.uk		CLIENT MR JOHN PRIDAY	PROJECT Proposed Dwelling	SITE ADDRESS Plot 101, Frittenden, Webbs Meadow. Adj. Upper House, Lyonshall, Herefordshire, HR5 3JN	DATE	08.06.21	SCALE		1:200.@.A3	
						DRAWN	DR	DRG. NO.	2011164.PRI-12	REV.	
						CHECKED	CA				