

Planting Schedule

KEY	Species	Girth (cm)	Height (cm)	Form	Clear Stem (cm)	Root	Qty
Ac	Acer campestre	16-18	450-625	Extra Heavy Standard	175-200	RB	9
ACs	Acer platanoides 'Crimson Sentry'	14-16	425-600	Extra Heavy Standard	175-200	RB	2
Am	Amelanchier lamarckii	14-16	300-350	Extra Heavy Standard	175-200	RB	11
Bp	Betula pendula	16-18	400-450	Extra Heavy Standard	175-200	RB	10
Bu	Betula utilis jacquemontii	-	300-350	Multi Stem, Bushy, 3 stems	-	RB	9
Cm	Crataegus monogyna	12-14	350-425	Heavy Standard	175-200	RB	8
Cl	Crataegus laevigata 'Paul's Scarlet'	12-14	350-425	Heavy Standard	175-200	RB	3
Fs	Fagus sylvatica 'Purpurea'	18-20	450-500	Extra Heavy Standard	200	RB	5
Lt	Liriodendron tulipifera	14-16	400-450	Extra Heavy Standard	175-200	RB	4
Pa	Prunus avium	12-14	350-450	Extra Heavy Standard	175-200	RB	3
Pd	Prunus domestica	14-16	400-450	Extra Heavy Standard	175-200	45L	14
Py	Pyrus calleryana 'Chanticleer'	16-18	400-450	Extra Heavy Standard	175-200	RB	6
Sa	Sorbus aucuparia	12-14	350-425	Heavy Standard	175-200	RB	16
Tg	Tilia cordata 'Greenspire'	18-20	400-450	Extra Heavy Standard	175-200	RB	24

Native Mix Hedgerow Planting

%	Species	Form	Height (cm)	Root	Qty
10	Cornus sanguinea	Transplant	60-80	BR	250
10	Rosa canina	Transplant	60-80	BR	250
25	Crataegus monogyna	Transplant	60-80	BR	610
15	Fagus sylvatica	Transplant	60-80	BR	366
15	Prunus domestica	Transplant	60-80	BR	366
10	Prunus spinosa	Transplant	60-80	BR	250
15	Sambucus nigra	Transplant	60-80	BR	366

Hedgerows are generally to be planted in double staggered rows 400mm apart at 5 per linear meter (400mm centres), unless stated otherwise on plans. Plants should be planted in single specie groups no less than 3 and no more than 5.

Native Thicket Mix 1

%	Species	Form	Height (cm)	Root	Density (Per m2)	Qty
25	Cornus sanguinea	Transplant	60-80	BR	2	201
15	Corylus avellana	Transplant	60-80	BR	2	119
10	Crataegus monogyna	Transplant	60-80	BR	2	80
15	Prunus domestica	Transplant	60-80	BR	2	119
15	Ligustrum vulgare	Transplant	60-80	BR	2	119
20	Sambucus nigra	Transplant	60-80	BR	2	162

Native thicket mix planting to be planting in single species groups no less than 5, no more than 7.

Native Thicket Mix 2 (Near Attenuation Basins)

%	Species	Form	Height (cm)	Root	Density (Per m2)	Qty
25	Cornus sanguinea	Transplant	60-80	BR	2	91
10	Crataegus monogyna	Transplant	60-80	BR	2	36
15	Ligustrum vulgare	Transplant	60-80	BR	2	54
20	Rhamnus frangula	Transplant	60-80	BR	2	72
15	Sambucus nigra	Transplant	60-80	BR	2	54
15	Viburnum opulus	Transplant	60-80	BR	2	54

Native thicket mix planting to be planting in single species groups no less than 5, no more than 7.

Ornamental Planting

Species	Height (cm)	Pot size	Form	Breaks per lower 1/3	Density	Qty
Bergenia cordifolia 'Purpurea'	-	2L	Full Pot	-	6	58
Cistus x pulverulentus 'Sunset'	30-40	3L	Bushy	5	3	62
Choisya 'Aztec Pearl'	30-40	5L	Bushy	6	3	10
Cornus alba 'Kesselringii'	60-80	5L	Branched	4	3	71
Deschampsia cespitosa 'Goldtau'	-	3L	Full Pot	-	4	24
Echinacea purpurea	-	2L	Full Pot	-	4	42
Geranium 'Johnson's Blue'	-	2L	Full Pot	-	4	27
Lavandula angustifolia 'Hidcote'	30-40	5L	Bushy	7	3	26
Philadelphus 'Manteau d'Hermine'	30-40	5L	Branched	5	2	17
Pittosporum 'Tom Thumb'	20-30	5L	Bushy	5	2	25
Sedum 'Autumn Joy'	-	3L	Full Pot	-	3	57
Spiraea japonica 'Anthony waterer'	30-40	5L	Branched	7	3	68
Stipa tenuissima	-	2L	Full Pot	-	5	158
Verbena bonariensis	-	2L	Full Pot	-	5	56

Plants to be planted in an evenly spaced but irregular pattern (i.e. no grids or straight lines).

Specimen Planting

Species	Height (cm)	Pot size	Form	Breaks per lower 1/3	Density	Qty
Sambucus 'Black Lace'	40-60	10L	Branched	4	As shown	2

Bulb Planting

Species	Density Per m2	Qty
Crocus chrysanthus 'Snow Bunting'	25	165
Crocus tommasinianus 'Whitewell Purple'	25	165
Narcissus 'Salome'	25	775
Narcissus 'Tete a Tete'	25	775

KEY

- Site Boundary

Existing trees retained in accordance with BS 5837:2012

Root Protection Areas (RPA)

Vegetation to be removed.

Proposed feature tree planting

Proposed structure tree planting

Proposed small native tree planting

Proposed native hedgerows

Proposed native shrub planting

Proposed ornamental shrub planting

Proposed specimen large shrubs

Areas of low maintenance amenity grass mix. Germinal (or similar) A22 Mix.

Proposed Wildflower Meadow Grass Mix Emorsgate EM2 Standard Meadow Mix (or similar)

Areas of proposed tussock long grass mix. Emorsgate (or similar) EM10 Mix.

Proposed Attenuation Basins sown with Wetland Tolerant Wildflower Grassland. Emorsgate EM8 (or similar).

Proposed bulb drifts in grass.
- Macadam surface footpaths.

Safety surfacing to LEAP play equipment. Bound rubber slied - Colour Green. Giffords Cushion Fall (or similar)

Signage to LEAP. Indicating the area is for childrens play and dogs are not welcome, contact details of facility operator and location.

Proposed seating. Furnitubes (or similar approved) Zenith Horizon Seat with Iroko timber slats and end arms.

Proposed litter bins. Furnitubes (or similar approved) Tenby Litter Bin, ref. TSL231, base mounted, galvanised steel and Iroko timber finish

Dog waste bins. Furnitubes (or similar approved) Lucky Dog Bin galvanised and powder coated in green LUK 745F

1000mm high vertical bar railings with gated access to LEAP. PPC galvanised steel. Colour Green.

600mm high Timber Knee Rail. Treated softwood.

Robinia Play Equipment to LEAP. See Landscape Masterplan for details - P20-1878_01.

Existing Foul Drain.

Extent of underground crated storm water storage system

Please refer to P20-1878_04 for Detailed On-Plot Planting Proposals.

Native Mix Hedgerow (38.35m long, quadruple staggered)
15% Fagus sylvatica 6nr.
10% Cornus sanguinea 4nr.
10% Rosa canina 4nr.
25% Crataegus monogyna 10nr.
15% Prunus domestica 6nr.
10% Prunus spinosa 4nr.
15% Sambucus nigra 6nr.

Native Thicket Mix 1
25% Cornus sanguinea 19nr.
15% Corylus avellana 11nr.
10% Crataegus monogyna 8nr.
15% Prunus domestica 11nr.
15% Ligustrum vulgare 11nr.
20% Sambucus nigra 15nr.

Native Thicket Mix 2
25% Cornus sanguinea 19nr.
15% Corylus avellana 11nr.
10% Crataegus monogyna 8nr.
15% Prunus domestica 11nr.
15% Ligustrum vulgare 11nr.
20% Sambucus nigra 15nr.

Native Mix Hedgerow (38m long, double staggered)
15% Fagus sylvatica 29nr.
10% Cornus sanguinea 19nr.
10% Rosa canina 19nr.
25% Crataegus monogyna 48nr.
15% Prunus domestica 29nr.
10% Prunus spinosa 19nr.
15% Sambucus nigra 29nr.

Native Mix Hedgerow (20m long, double staggered)
15% Fagus sylvatica 15nr.
10% Cornus sanguinea 10nr.
10% Rosa canina 10nr.
25% Crataegus monogyna 25nr.
15% Prunus domestica 15nr.
10% Prunus spinosa 10nr.
15% Sambucus nigra 15nr.

NOTES

Please refer to P20-1878_02 Sheet 3 for the Planting Specification.

POS Detailed Landscape Proposals

Canon Pyon Road, Hereford

Client: Taylor Wimpey

DRWG No: P20-1878_02 Sheet: 2 REV: G

Drawn by: RL/IHW

Approved by: NH

Date: 10/08/2021

Scale: 1:200 @ A1

Pegasus Design

Revisions:
First Issue: 03/11/2020 RL
A: 21/01/2021 IHW Amended following ecology comments
B: 08/06/2021 IHW Amended following LPA comments
C: 18/06/2021 IHW - Amended following client comments
D: 22/06/2021 NH - Update to POS
E: 07/07/2021 IHW - Additional planting to POS
F: 16/07/2021 IHW - Street furniture added to western POS
G: 10/08/2021 IHW - Layout amended to accommodate footpath to shared roads, tree survey updated, landscaping amended to vis splays