

no.5 south west elevation



no.6 south east elevation



- new low profile metal rooflights over (The Rooflight Company web: http://www.the rooflightcompany.co.uk/the-conservation-(21 rooflight-product)
- 28 existing prefab classroom extension to be reclad using a planed vertical board
- (29) existing windows replaced with new double-glazed, powder-coated aluminium frame windows
- (36) existing roof finish replaced with corugated/ profiled metal sheet roofing system
- existing single-glazed, sliding sash timber
  windows to be repaired, overhauled and
  upgraded to full working order and redecorated
- single glazed timber casement windows to be repaired, overhauled and upgraded to full working order and redecorated all ledges and projections to decorative cornice, balustrading and copers etc. to be cleaned to remove lichen and moss growth by specialist cleaning contractor using DOFF/JOSS/TORC
- cleaning system 56 new 100mm Ø cast iron/ uPVC soil vent pipes, colour: black
- isolated patch repointing, using a 1:2.5 NHL 2.5 naturally hydraulic lime mortar mix using purpose made / proper pointing tools that fit the joint width to ensure good compaction and remove all mortar droppings immediately
- plaster repair to decorative cornice using a 1:2.5 NHL 2.5 naturally hydraulic lime mortar mix
- masonry to be cleaned by specialist contractor to remove organic growth following removal of dead creepers/ root systems using DOFF/JOSS/TORC cleaning system
- ★ all roofs, ledges, gutters and valleys to be cleaned and all moss/ lichen growth to be removed and area treated using ROUNDUP PRO VANTAGE



